

PROJECT: Kevin
ADDRESS:
SECTIONS: ALL

PROJECT FILENAME: MCNULTY, KEVIN 3
ARCHITECT:

Metal Panels Summarized by Section

Section A - 40.00' X 16.00" 16" Image II

Surface Area = 3807.25 SQR FT

LINEAR FEET	QUANTITY	% WASTE	TOTAL LN. FEET	SQUARE FEET
20'5"	18	0.4	367'6"	490.0
20'0"	1	3.6	20'0"	26.7
19'11"	2	3.6	39'10"	53.1
19'6"	1	3.7	19'6"	26.0
19'5"	1	3.7	19'5"	25.9
19'0"	1	3.8	19'0"	25.3
18'7"	1	3.9	18'7"	24.8
18'5"	2	3.9	36'10"	49.1
18'3"	2	26.2	36'6"	48.7
18'1"	1	4.0	18'1"	24.1
18'0"	1	4.0	18'0"	24.0
17'11"	1	4.0	17'11"	23.9
17'7"	1	4.1	17'7"	23.4
17'2"	1	5.3	17'2"	22.9
17'1"	1	4.2	17'1"	22.8
17'0"	2	4.2	34'0"	45.3
16'8"	1	4.3	16'8"	22.2
16'7"	1	4.4	16'7"	22.1
16'6"	1	4.4	16'6"	22.0
16'1"	1	4.6	16'1"	21.4
15'8"	1	4.5	15'8"	20.9
15'7"	2	4.6	31'2"	41.6
15'2"	1	4.8	15'2"	20.2
15'1"	1	4.8	15'1"	20.1
15'0"	2	7.2	30'0"	40.0
14'6"	1	10.0	14'6"	19.3
14'5"	27	1.0	389'3"	519.0
14'1"	2	5.1	28'2"	37.6
13'9"	1	5.3	13'9"	18.3
13'8"	2	4.4	27'4"	36.4
13'7"	1	5.3	13'7"	18.1
13'6"	1	5.3	13'6"	18.0
13'0"	14	1.7	182'0"	242.7
12'11"	2	5.6	25'10"	34.4
12'8"	2	4.4	25'4"	33.8
12'5"	1	5.8	12'5"	16.6
12'4"	1	5.9	12'4"	16.4
12'3"	15	2.3	183'9"	245.0
12'2"	2	11.9	24'4"	32.4
12'1"	1	6.0	12'1"	16.1
11'7"	8	7.0	92'8"	123.6
11'6"	2	6.3	23'0"	30.7
11'3"	1	6.4	11'3"	15.0
11'0"	1	6.6	11'0"	14.7
10'10"	1	6.7	10'10"	14.4
10'9"	3	6.7	32'3"	43.0
10'7"	1	6.8	10'7"	14.1

10'2"	7	7.1	71'2"	94.9
10'1"	3	4.9	30'3"	40.3
9'9"	1	7.4	9'9"	13.0
9'8"	1	7.5	9'8"	12.9
9'6"	1	7.6	9'6"	12.7
9'5"	7	4.4	65'11"	87.9
9'4"	3	7.7	28'0"	37.3
9'3"	3	13.0	27'9"	37.0
9'2"	1	7.9	9'2"	12.2
8'8"	12	9.0	104'0"	138.7
8'7"	2	8.4	17'2"	22.9
8'6"	1	8.5	8'6"	11.3
8'4"	1	8.7	8'4"	11.1
8'3"	1	8.8	8'3"	11.0
8'1"	1	8.9	8'1"	10.8
8'0"	3	9.0	24'0"	32.0
7'11"	3	9.1	23'9"	31.7
7'10"	1	9.2	7'10"	10.4
7'9"	1	9.3	7'9"	10.3
7'3"	11	10.0	79'9"	106.3
7'2"	2	10.1	14'4"	19.1
7'1"	1	10.2	7'1"	9.4
6'11"	1	10.4	6'11"	9.2
6'10"	1	10.6	6'10"	9.1
6'8"	1	10.8	6'8"	8.9
6'6"	3	11.1	19'6"	26.0
6'5"	3	11.3	19'3"	25.7
6'4"	3	19.0	19'0"	25.3
6'3"	1	11.6	6'3"	8.3
5'10"	12	13.4	70'0"	93.3
5'9"	2	12.6	11'6"	15.3
5'8"	1	12.7	5'8"	7.6
5'5"	1	13.3	5'5"	7.2
5'4"	1	13.5	5'4"	7.1
5'2"	1	14.0	5'2"	6.9
5'1"	3	14.2	15'3"	20.3
5'0"	3	14.4	15'0"	20.0
4'11"	1	14.7	4'11"	6.6
4'10"	1	14.9	4'10"	6.4
4'4"	11	16.7	47'8"	63.6
4'3"	2	17.0	8'6"	11.3
4'2"	1	17.3	4'2"	5.6
4'0"	65	18.0	260'0"	346.7
-----			-----	-----
SUBTOTAL	323 Panels		3187'6"	4250.0
=====			=====	=====
PAN. TOTAL	323 Panels		3187'6"	4250.0

Metal Panel Items Summarized by Section

Section A

ITEM	UNITS	ORDER INFO
#10 x 1" PNCK Screw (100/bag)	39 Bag	

Overlap Items Summarized by Section

Substrate Items Summarized by Section

Details Summarized by Section

Section A

DETAIL	UNITS	ANGLE	ORDER INFO
Standing Seam Valley	8.0 PIECES	148.4°	
Standing Seam Endwall	1.0 PIECES	112.6°	
Standing Seam Sidewall	2.0 PIECES	90.0°	
Standing Seam Eave	32.0 PIECES	112.6°	
Standing Seam Hip	19.0 PIECES	148.4°	
Standing Seam Ridge	8.0 PIECES	134.8°	

Detail Items Summarized by Section

Section A

ITEM	UNITS	ORDER INFO
Butyl Tape (40' roll)	4 Roll	
Universal Foam Closure (25')	19 Roll	
Z Closures for Ridge Cap	66 Each	
#10 x 1" PNCK Screw (100/bag)	5 Bag	
#9 x 1" Wood Screw (100/bag)	1 Bag	
#14 Stitch Screw (100/bag)	6 Bag	

Extras Summary

DESCRIPTION	UNITS
-------------	-------

Total Surface Area = 3807.25 SQR FT